ENGINEERING DEPARTMENT.

HASSAN DIVISION.

Notice dated 4th June 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 5 P.M. on 22nd June 1929, for restoring Chinnenahalli Mekere R. No. 198, Belur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed in one season or by end of June 1930.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest-money and be superscribed "Tender for constructing Chinnenahalli Mekere R. No. 198, Belur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract for restoring Chinnenahalli Mekere Registered No. 198, Belur Taluk, Hassan District :—

No.	Items of work	Per	Quantity
	Bund R. L. 55·00		
1	Earthwork to bund with consolidation	C.yd.	1505
2	Turfing the slopes	S.yd.	1605
3	Grade and Index stones	No.	6
4	Date and Registered number stone	,,	1
5	B. M. stones	,,	2
	Sluice R. L. 47·00.		
1	Cut open the bund and refilling the same with consolidation ...	C.yd.	28
2	Metal concrete in surki mortar	C.ft.	100
3	Burnt brick in surki mortar	,,	94
4	Plastering with surki mortar	Sqr.	1·13
5	Burnt stone slabs 6" thick dressed	S.ft	45.
6	New stone work	C.yd.	2
7	Cast iron pipe 4" dia 36' long including carrying and fixing, etc., complete.	R.ft.	24
8	Cutting holes in gibbet slabs and providing gear rod ...	Lump	sum
	Waste Weir R. L. 50·00.		
1	Earthwork excavation foundation	C.yd.	9
2	Clearing draft	Lump	sum
3	Concrete in surki mortar	C.ft.	80
4	Burnt brick in surki mortar	,,	44
5	Plastering with surki mortar	Sqr.	0·24
6	Burnt stone slabs 6" thick dressed	S.ft.	41
7	Rough stone work new	C.yd.	23

N. KRISHNIENGAR,
Executive Engineer.